

STREET	LOCATION DESCRIPTION	FLOW TYPE	WORK NAME TYPE	EST COST	COMMENTS	DIAMETER	LENGTH
BALMORAL ST	1ST MH S OF SARGENT AV TO MH AT QU'APPELLE AV	CS	FULL SEGMENT LINER	\$49,500.00	B, FM, FL, CM, CC, CL, SSS	375	79.4
CHURCH AV	1ST MH W MCGREGOR AV - MH @ MCGREGOR AV	CS	FULL SEGMENT LINER	\$71,250.00	FL, CL, B, D 5%	450	100.0
FURBY ST	2ND MH S OF PORTAGE AV TO 3RD MH S OF PORTAGE AV	CS	FULL SEGMENT LINER	\$23,250.00	FC, CC, FLx4, D - images available; B, FM, CM. Proximity to gas main	300	34.2
FURBY ST	4TH MH S OF SARGENT AV TO MH AT ELLICE AV	CS	FULL SEGMENT LINER	\$71,250.00	B, FM, CM, CC, CL, JOM, SSS	450	99.6
KILDARROCH ST	1ST MH N OF MOUNTAIN AV. TO MH AT MOUNTAIN AV.	CS	FULL SEGMENT LINER	\$64,725.00	Street is being renewed in 2022 and the sewer is in poor condition so lining in the near future is advised to avoid having to dig up the new pavement	300	108.1
LANGSIDE ST	MH AT NOTRE DAME AV(SPL) TO 1ST MH S OF NOTRE DAME AV	CS	FULL SEGMENT LINER	\$58,425.00	B, DR 5%, FM, CM	300	96.6
LANDSDOWNE AV	1ST MH E OF AIKENS ST TO 2ND MH E OF AIKENS ST	CS	FULL SEGMENT LINER	\$56,437.50		450	86.4
MCGEE ST	MH AT SARGENT AV(SPL) TO 1ST MH S OF SARGENT AV	CS	FULL SEGMENT LINER	\$58,950.00	FM, FL, CC, CL, SSS, ID	375	97.7
MOUNTAIN AVE	MH @ TINNIS WOOD ST(CL)-MH @ RADFORD ST	CS	FULL SEGMENT LINER	\$62,325.00	FL, FC	450	85.4
PIONEER AV	3RD MH W OF WESTBROOK ST TO 4TH MH W OF WESTBROOK ST	CS	FULL SEGMENT LINER	\$39,525.00	FL, SWS	300	60.6
RADFORD ST	1ST MH N OF MOUNTAIN AVE-MH @ MOUNTAIN AVE	CS	FULL SEGMENT LINER	\$60,525.00	FL, HJ, SSMJ	375	100.4
REDWOOD AVE	MH AT CHARLES ST CL TO 1ST MH W CHARLES ST	CS	FULL SEGMENT LINER	\$60,525.00	FCJ	300	100.4
SHERBROOK ST	1ST MH AT PORTAGE AV TO 2ND MH N OF PORTAGE AV	CS	TRENCHLESS PT REPAIR	\$17,400.00	FC - image available; DR 10%, B, FM	300	3.0
SHERBROOK ST	3RD MH S OF NOTRE DAME AV TO 1ST MH S OF CUMBERLAND AV	CS	FULL SEGMENT LINER	\$51,075.00	03,10,12,FC,FJ,D-10%,CL,CV SERVICE THRU SEWER @76.5m, RESHOOT SERVICE (Ver	300	82.4
SPENCE ST	MH AT SARGENT AV TO 1ST MH S OF SARGENT AV	CS	FULL SEGMENT LINER	\$64,875.00	HVV, MB, FL, FM, FC, DR	450	89.9
TINNISWOOD ST	1ST MH N OF MOUNTAIN AVE-MH @ MOUNTAIN AVE(CL)	CS	AUGMENTED FS LINER	\$100,350.00	FL x 2, FLJ, FCJ Street is being renewed in 2022 and the sewer is in poor condition so lining in the near future is advised to avoid having to dig up the new pavement if defects worsen EPR 21.9 - 24.2 m DS (reconnect service) EPR 34.8 - 37.1 m D	375	55.0
BEATRICE ST	1ST MH S OF COBOURG AV TO MH AT COBOURG AV	CS	FULL SEGMENT LINER	\$26,850.00	Proximity to feeder main	300	43.0
BELAIR RD (S. LEG)	MH AT BELAIR RD(E. LEG) TO MH AT MARSHALL BY(W. LEG)	LDS	FULL SEGMENT LINER	\$56,550.00	DR 10%, BSV, FM, JOM, CM, CC, SRI, SSS, IDJ	300	108.3
BROCK ST	MH AT GRANT AV TO 1ST MH S OF GRANT AV	CS	FULL SEGMENT LINER	\$58,425.00		375	96.6
BROCK ST	MH AT GRANT AV TO 1ST MH N OF GRANT AV	CS	FULL SEGMENT LINER	\$59,475.00		375	98.6
CARPATHIA DR	1ST MH E OF KENASTON BV. TO MH AT CARPATHIA DR.	CS	FULL SEGMENT LINER	\$34,800.00	Street rehab in 2022. FSL assigned to address point defect at 0-2.0m in D/S direction. EPR & FSL costs similar.	300	51.8
CHALMERS AV	1ST MH W OF ROCH ST TO 2ND MH W OF ROCH ST	CS	FULL SEGMENT LINER	\$21,000.00	Proximity to feeder main	300	30.0
CHERRIER ST()	1ST MH W OF ARCHIBALD ST TO MH AT ARCHIBALD ST	CS	FULL SEGMENT LINER	\$22,725.00	SS. Stabilization required at 0-1m	300	28.4
DE MEURONS AV	MH AT DUBUC ST TO 1ST MH S OF DUBUC ST	CS	FULL SEGMENT LINER	\$46,500.00	FL/CL THROUGHOUT - IMAGES AVAILABLE. Proximity to gas main	375	79.2
DE MEURONS AV	1ST MH S OF DUBUC ST TO MH AT YARDLEY ST	CS	FULL SEGMENT LINER	\$46,500.00	FM, FL	375	79.4
DE MEURONS AV	MH AT YARDLEY ST TO MH AT NIVERVILLE AV	CS	FULL SEGMENT LINER	\$47,475.00	FM	375	81.5
DEARBORN AV	MH AT LACY ST TO MH AT BRAZIER ST	CS	FULL SEGMENT LINER	\$13,350.00	FM, B, H, D. Proximity to gas main	300	12.0
DUBUC ST	MH AT BRAEMAR AV(E OF CL) TO MH AT BRAEMAR AV(CL)	CS	FULL SEGMENT LINER	\$9,900.00	TPR changed to FSL. Segment within PWD 2022 Street Renewal, should line as pipe showing signs of deterioration (2.5 - 3.5m)	450	3.6
EASEMENT(E OF	1ST MH N OF CRANE AV TO MH AT CRANE AV	LDS	FULL SEGMENT LINER	\$67,462.50	DR 10%, BSV, FM, FC, CC, CL, JOM, SAP, SRI, SSS	300	122.5
EUGENIE ST(CL)	3RD MH N OF DES MEURONS-MH @ YOUNVILLE ST	CS	FULL SEGMENT LINER	\$39,450.00	FL @ 06, SSL @ INVERT, SSL/H @ 03, B @ 05, FC, SSMJ, FL @ 03 & 09 - images available. Proximity to feeder main	300	70.1
GRANT AV (N OF	NODE W OF CORDOVA ST TO MANHOLE AT CORDOVA ST	CS	FULL SEGMENT LINER	\$12,750.00		300	9.7
HALLIDAY BY NL	MH @ HALLIDAY BY ELEG - MH @ SPEERS RD	WWS	FULL SEGMENT LINER	\$62,100.00		200	112.0
HALLIDAY BY S L	MH AT HALLIDAY BY E LEG TO MH AT SPEERS RD	WWS	AUGMENTED FS LINER	\$76,095.00	H DIG DOWN FROM 93.0M - 95.0M, DS. Proximity to feeder main	200	112.5
HARBISON AV W	1ST MH W OF ROCH ST TO 2ND MH W OF ROCH ST	CS	FULL SEGMENT LINER	\$53,400.00		300	101.7
HARVARD AV W	MH AT WINONA ST TO 1ST MH W OF BOND ST	WWS	AUGMENTED FS LINER	\$68,220.00	EPRs THROUGHOUT: -12.6 - 14.6m; 26.08 - 28.08m added to 2022 Capital because pavement work at Winona dictates attention	200	87.3
HILL ST.	1ST MH S OF DUBUC ST. TO 2ND MH S OF DUBUC ST.	CS	FULL SEGMENT LINER	\$53,100.00	DR 5%, FM, CM, CC, CL, SAM, SAP, SAV, SRI	450	75.3
HILL ST.	2ND MH S OF DUBUC ST. TO MH AT NIVERVILLE AV	CS	FULL SEGMENT LINER	\$54,750.00	FL, CM, CL, SAV	450	83.9
HILLCREST AV	1ST MH S OF NIVERVILLE AV TO MH AT CATON ST	CS	FULL SEGMENT LINER	\$57,450.00	FL; SOME D<10% - IMAGES AVAILABLE	300	110.7
HORACE ST	1ST MH W OF YOUNVILLE ST TO MH AT YOUNVILLE ST	CS	FULL SEGMENT LINER	\$56,550.00	Laist 10.0m within PWD 2022 Street Renewal, should line as pipe showing signs of deterioration (Spalling - Agg Visible)	300	108.2
LA GRAVE ST	1ST MH N OF LORD AV TO MH AT LEMAY AV	LDS	FULL SEGMENT LINER	\$50,700.00	BSV, B, DR 10%, FM, FL, CC, CL, SRI, SSS	375	95.3
LAWDALE AV	1ST MH N OF LYNDALE DR TO MH AT CONISTON ST	CS	FULL SEGMENT LINER	\$70,050.00	STREET RENEWED IN 2022 AND POST REPAIR VIDEO SHOWS SOME DEFORMATION AND 4 POINT CRACKING AT 50 METRES JUST BEFORE START OF CL	300	138.1
MADELINE ST	MH AT KILDARE AV W NPL TOMH AT KILDARE AV W CL	WWS	FULL SEGMENT LINER	\$11,887.50	Street rehabbed in 2021 - should line before defects worsen and a dig under new pavement is required.	250	8.4
NOBLE AV	3RD MH W OF HENDERSON HWY TO MH AT BEATRICE ST	CS	FULL SEGMENT LINER	\$51,600.00	Proximity to feeder main	375	97.3
NOTTINGHAM AV	1ST MH W OF BESANT ST TO 2ND MH W OF BESANT ST	CS	FULL SEGMENT LINER	\$59,700.00	Proximity to feeder main	300	115.8
PARKER AV	1ST MH W OF DANIEL ST TO MH AT DANIEL ST EPL	CS	FULL SEGMENT LINER	\$47,100.00	PARTIAL LINER, HJ, SWL/HJ X 2, FL @ 09, FC, FL @ 03, BJ - images available. Proximity to gas main	300	87.3
PILGRIM AV	MH @ DES MEURONS ST (EPL) TO MH @ DES MEURONS ST	WWS	FULL SEGMENT LINER	\$11,887.50	FL, FM. Proximity to gas main	300	8.1
PROVENCHER BL	2ND MH W OF ST JEAN BAPTISTE-MH @ LANGEVIN (CL)	CS	FULL SEGMENT LINER	\$78,262.50		450	110.3
PROVENCHER BL	MH AT THIBAUT ST TO 1ST MH W OF THIBAUT ST	CS	FULL SEGMENT LINER	\$69,975.00	FL THROUGHOUT - IMAGES AVAILABLE	375	118.1
RUE AUBERT	MH AT GABRIELLE ROY PL TO CERCLE MOULIERE	WWS	AUGMENTED FS LINER	\$83,250.00	DPE 5-10%, FM, FL - EPR 84.2M TO 91.9M (7.7M) H, DFE 5-20%, FM, FL, FC, IGB, IRB - 3 POINTS OF WATER INFILTRATION	250	99.1
RUE LANGEVIN	1ST MH N OF HAMEL AV TO MH AT HAMEL AV	CS	FULL SEGMENT LINER	\$18,712.50	FL THROUGHOUT- SOME D <10% - IMAGES AVAILABLE check depth 2021 UPDATE: U-SIPHON 14.9M DS CROSSING WM; B, DR 5%, FM, CM, CL, CC	300	22.6
RUE ST.JOSEPH	1ST MH N OF PROVENCHER BV.	CS	FULL SEGMENT LINER	\$31,387.50	PARTIAL RELINE FROM US MH - FL/SSM - IMAGES AVAILABLE 2021 CONDITION ASSESSMENT UPDATE: HSV, FM, FL, CM, CL, CC, SAM, SAP; DROP PIPE @ 47.6M	250	48.6
SPEERS RD	1ST MH N OF CRESTWOOD CRTO2ND MH N OF CRESTWOOD CR	WWS	FULL SEGMENT LINER	\$52,500.00		250	99.8
TACHE AV.	MH AT RUE MESSENGER TO MH AT RUE HEBERT	CS	FULL SEGMENT LINER	\$67,687.50	FL X4 FROM 15 TO 22 AND FROM 64 TO 104 - IMAGES AVAILABLE UPDATE: B, FM, CM, CL, SAV, SSS. Proximity to aqueduct	450	107.0
WATERFORD AV	3RD MH E OF PEMBINA HWY TO 4TH MH E OF PEMBINA HWY.	LDS	FULL SEGMENT LINER	\$57,450.00	associated pending EPR added to 2022 PWD prog	375	110.3
WATERFORD AV	4TH MH E OF PEMBINA HWY TO MH AT WICKLOW ST.	LDS	FULL SEGMENT LINER	\$57,450.00		375	110.6
WHITTIER AV W	1ST MH W OF WINONA ST TO MH AT WINONA ST	WWS	FULL SEGMENT LINER	\$64,125.00		200	75.0
WILLIAM NEWBY	MH AT ALLEN ST TO 1ST MH E OF ALLEN ST	CS	FULL SEGMENT LINER	\$51,600.00	CL, CM, FL, FM, B, D. Proximity to gas main	300	97.1
WINONA ST	MH AT HARVARD AV W TO MH AT WHITTIER AV W	WWS	FULL SEGMENT LINER	\$47,100.00	2022 street renewal, FSL req'd on sewer before defects worsen, and dig is req'd under new pavement.	200	87.2
WESTGROVE W	MH @ PEPPERTREE PL TO 1ST MH E OF PEPPERTREE PL	WWS	FULL SEGMENT LINER	\$25,950.00	SPALLING--LOTS OF SPALLING SHOULD HAVE BEEN SCORED HIGHER THAN SPG 3	200	87.9
MCMICKEN ST	1ST MH N. OF SARGENT AV. TO MH AT SARGENT AV.	CS	FULL SEGMENT LINER	\$52,125.00	Street is being renewed in 2023 and the sewer is in poor condition so lining in the near future is advised to avoid having to dig up the new pavement	225	84.6

\$3,015,765.00