











TREE PLANTING SCHEDULE					
SYMBOL	COMMON NAME	BOTANICAL NAME	SIZE AND REMARKS	QTY	SPACING
	Trembling Aspen	<i>Populus tremuloides</i>	50mm Caliper, min 3050 mm Ht., min. Well-branched and balanced, min. 10 major branches 1200mm above grade. 600mmØ rootball. B&B or tree mover, wire basket.	8	As Shown
	Harvest Gold Linden	<i>Tilia mongolica 'Harvest Gold'</i>	50mm Caliper, min 3050 mm Ht., min. Well-branched and balanced, min. 10 major branches 1200mm above grade. 600mmØ rootball. B&B or tree mover, wire basket.	1	As Shown
	Black Hill Spruce	<i>Picea glauca 'Densata'</i>	B&B, min 1800mm ht., min 600mm base width. Single upright (no broken) leader, well-branched, full form 360" to grade.	3	As Shown
SHRUB & PERENNIALS PLANTING SCHEDULE					
SYMBOL	COMMON NAME	BOTANICAL NAME	SIZE AND REMARKS	QTY	SPACING
	Little Rebel Dogwood	<i>Cornus alba 'Jefreb'</i>	#2 container. 400-500mm Height. Well developed root system. Full, bushy plant.	22	1.2m OC
	Gro-Low Sumac	<i>Rhus aromatica 'Gro-Low'</i>	#2 container. 400-500mm Height. Well developed root system. Full, bushy plant.	111	1.0m OC
	Baby Joe Dwarf Joe Pye Weed	<i>Eupatorium dubium 'Baby Joe'</i>	#1 container.	34	500mm OC
	Black-Eyed Susan	<i>Rudbeckia fulgida 'Goldstrum'</i>	#1 container.	26	500mm OC
	Walker's Low Catmint	<i>Nepeta faassenii 'Walker's Low'</i>	#1 container.	38	500mm OC

- NOTES:**
- GENERAL NOTES**
- ALL DIMENSIONS ARE IN INCHES UNLESS NOTED OTHERWISE
 - ALL EXISTING STRUCTURES, TREES, SHRUBS, SIDEWALKS, CURBS, SOD, UTILITIES AND PAVING TO BE PROTECTED (UNLESS OTHERWISE NOTED) DURING CONSTRUCTION. CONTRACTOR TO MAKE GOOD ALL DAMAGED AREA DURING CONSTRUCTION BOTH ON AND OFF SITE TO OWNER'S STANDARDS AT THE CONTRACTOR'S COST
 - CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION
 - CONTRACTOR TO CONFIRM ALL BUILDING LOCATIONS, LAYOUT, DIMENSIONS AND MATERIALS ON SITE AND REPORT ANY DISCREPANCIES TO THE CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION
 - CONTRACTOR TO PROTECT ALL EXISTING TREES UNLESS OTHERWISE NOTED OR DIRECTED BY CONTRACT ADMINISTRATOR
 - ALL PROPOSED LAYOUT TO BE APPROVED BY CONTRACT ADMINISTRATOR PRIOR TO ANY CONSTRUCTION OR REMOVAL
 - ALL NOTES IN GREY INDICATED ITEMS NOT IN CONTRACT (NIC)

0	25 / 05 / 16	ISSUED FOR TENDER	SK
REV	YY / MM / DD	DESCRIPTION	BY

<p>A. SECTION LETTER OR DETAIL NUMBER</p> <p>B. DRAWING WHERE SECTION OR DETAIL IS DRAWN.</p> <p>OR</p> <p>DRAWING WHERE SECTION OR DETAIL IS INDICATED.</p> <p>--- SECTION OR DETAIL SHOWN ON SAME DRAWING.</p> <div style="display: flex; justify-content: space-around; align-items: center;"> <div style="text-align: center;">  </div> <div style="text-align: center;">  </div> </div>	<p>PROFESSIONAL'S SEAL</p>
--	----------------------------

SCATLIFF + MILLER + MURRAY
visionary urban design + landscapes

CONSULTANT FIRM NAME
CLIENT
<p>CITY OF WINNIPEG PLANNING, PROPERTY & DEVELOPMENT</p>  <p>ODEON PARK REDEVELOPMENT</p>

PLANTING PLAN			
DESIGN	DRAWN	DATE - Y / M / D	SCALE
SK/CT	CT	25/05/16	1:125
CHECKED	APPROVED	PROJECT No.	DRAWING No.
SK	SK	23-2687-006	L400