

ASSET NUMBER	STREET	LOCATION DESCRIPTION	FLOW TYPE	WORK NAME TYPE	ESTIMATED COST	COMMENTS	DIAMETER	LENGTH
S-MA40008779	ALLAN ST (CL)	MH AT THAMES AV TO TEE IN MAIN	CS	FULL SEGMENT LINER	\$44,947.25	Street is being renewed in 2025 and the sewer is in poor condition so lining in the near future is advised to avoid having to dig up the new pavement if defects worsen	300	92.4
S-MA50011462	BARRINGTON AV (NPL)	2ND MH W OF ST MARYS RD TO 3RD MH W OF ST MARYS RD	LDS	FULL SEGMENT LINER	\$61,157.75	Street is being renewed in 2025 and the sewer is in poor condition so lining in the near future is advised to avoid having to dig up the new pavement if defects worsen	300	120.3
S-MA60009769	CARTER AV.	MH AT ARBUTHNOT ST TO 1ST MH W OF ARBUTHNOT ST.	CS	FULL SEGMENT LINER	\$43,208.50	B, FM, FL, CRACKS, 5-10% DAE, 5-30% DAGS, JOM, RFC/ RFJ, SAV, SSS	300	87.6
S-MA60011962	CARTER AVE	1ST MH W OF ARBUTHNOT ST TO MH AT LILAC ST	CS	FULL SEGMENT LINER	\$42,513.00	HVV AND B AT TB.	300	85.0
S-MA60015751	CHANCELLOR DR	MH AT ALUMNI PL (E.LEG) TO MH AT ALUMNI PL (W.LEG)	WWS	FULL SEGMENT LINER	\$28,335.50	Street is being renewed in 2025 and the sewer is in poor condition so lining in the near future is advised to avoid having to dig up the new pavement if defects worsen	250	73.7
S-MA60022267	CLOUIER DR	2NDMH W OF STORMONT DR TO 1ST MH W OF STORMNOTDR	WWS	FULL SEGMENT LINER	\$32,615.50	SSM	250	93.6
S-MA40005951	CORINNE ST	MH AT CEDARCREST DR TO MH AT MARK PEARCE AV	CS	FULL SEGMENT LINER	\$86,822.90	SSS-SSM THRU-OUT (MOD-SEVERE CORROSION), CL, FL, CX'S, POORLY GRADED	525	84.6
S-MA50003411	CROMWELL ST.	1ST MH W.OF ST.MARYS RD TO TIE-IN AT ST.MARYS RD.	CS	FULL SEGMENT LINER	\$33,872.75		300	52.9
S-MA40006592	DUNROBIN AV	MH AT ROCH ST WPL TO 1ST MH W OF ROCH ST	CS	FULL SEGMENT LINER	\$45,295.00	CL, CM, FL, SSL	300	93.5
S-MA40006456	DUNROBIN AV (CL)	1STMH E OF HENDERSONHWYTO2NDMH E OF HENDERSONHWY	CS	FULL SEGMENT LINER	\$46,686.00	CL, CM, SSL, D	300	97.8
S-MA60002078	ELDRIDGE AV	1ST MH E OF LAXDAL RD TO MH AT MAYFIELD CR W PL	WWS	FULL SEGMENT LINER	\$27,051.50	Advanced surface wear, JOM, F	250	68.0
S-MA60002565	ELDRIDGE AV	MH AT HEWITT CR TO 1ST MH W OF HEWITT CR	WWS	FULL SEGMENT LINER	\$32,401.50	Advanced surface wear, broken	250	92.7
S-MA70031795	ELDRIDGE AV	1ST MH W OF HEWITT CR TO MH AT HANEY ST	WWS	FULL SEGMENT LINER	\$33,257.50	SAM, pipe very eroded	250	97.0
S-MA60001920	ELDRIDGE AVE	MH AT LAXDAL RD. TO 1ST MH E.OF LAXDAL RD.	WWS	FULL SEGMENT LINER	\$30,689.50	Advanced surface wear, JOM, FM	250	84.4
S-MA40008809	GORDON AV.	2ND MH E OF LACY ST TO 1ST MH E OF LACY ST.	CS	FULL SEGMENT LINER	\$47,729.25	Multiple fractures and cracks throughout, broken pipe, offset joints....	300	100.5
S-MA50015119	HASTINGS BV (CL)	1ST MH W OF DUNKIRK DR TO 1ST MH E OF DUNKIRK DR	WWS	FULL SEGMENT LINER	\$27,907.50	SAM	250	63.7
S-MA60019130	HAZEL PRK DR.(N.LEG)	1ST MH W OF GROVELAND BY.(E.LEG)TO GROVELAND BY.(E.LEG)	WWS	FULL SEGMENT LINER	\$35,825.50	CROSSBORE A2 93.3M DS. HSV, BSV, B, MULT FM, FC, CL, CC, SAP, SAV, SSS, 5% ROOTS/ OBI, 5-10% DAE, 5% DAGS	250	108.9
S-MA60011774	HECTOR AV	1ST MH E OF STAFFORD ST TO 2ND MH E OF STAFFORD ST	CS	FULL SEGMENT LINER	\$44,305.25	5% DR, FRACTURES, AND CRACKS, 5% DAE, RFJ	300	78.3
S-MA60011919	HECTOR AV	MH AT WENTWORTH ST TO 1ST MH E OF WENTWORTH ST	CS	FULL SEGMENT LINER	\$42,860.75	10% DR, FH4, CM, CC, 10-55% DAE, RFJ, SSS	375	86.6
S-MA60011913	HECTOR AV.	1ST MH E.OF WENTWORTH ST TO MH AT ULAC ST.	CS	FULL SEGMENT LINER	\$42,860.75	FM 51-64m	375	86.3
S-MA50006270	JUBINVILLE BY E LEG	1ST MH N OF JUBINVILLE BY S LEG TO MH AT BETOURN	WWS	FULL SEGMENT LINER	\$26,195.50	Part of street is being renewed in 2025 and the sewer is in poor condition so lining in the near future is advised to avoid having to dig up the new pavement if defects worsen	200	64.0
S-MA50006267	JUBINVILLE BY W LEG	MH AT JUBINVILLE BY S LEG TO 1ST MH N OF JUBINVI	WWS	FULL SEGMENT LINER	\$26,409.50	Street is being renewed in 2024 and the sewer is in poor condition so lining in the near future is advised to avoid having to dig up the new pavement if defects worsen. (Sewer mostly runs just outside	200	64.8
S-MA40011862	KANATA ST	MH AT REGENT AV E TO MH AT VICTORIA AV E	WWS	FULL SEGMENT LINER	\$32,187.50		200	91.6
S-MA40013775	KANATA ST	MH AT YALE AV E TO MH AT RAVELSTON AV E	WWS	FULL SEGMENT LINER	\$31,759.50	Street is being renewed in 2024 and the sewer is in poor condition from 13.4-20.7m so lining in the near future is advised to avoid having to dig up the new pavement if defects worsen	200	89.3
S-MA40013938	KERN CR(N LEG)	1ST MH N OF ROSSEAU AV E TO 1ST MH W OF WABASHA ST	WWS	FULL SEGMENT LINER	\$24,269.50	Street is being renewed in 2024 and the sewer is in poor condition so lining in the near future is advised to avoid having to dig up the new pavement if defects worsen	200	54.9
S-MA40013943	KERN DR	1ST MH S OF ROSSEAU AV E TO 1ST MH NW OF ROSSEAU AV E	WWS	FULL SEGMENT LINER	\$24,911.50	Street is being renewed in 2024 and the sewer is in poor condition so lining in the near future is advised to avoid having to dig up the new pavement if defects worsen	200	57.6
S-MA40013944	KERN DR(E.LEG)	1ST MH NW OF ROSSEAU AV E TO 1ST MH E OF WABASHA ST	WWS	FULL SEGMENT LINER	\$24,911.50	Street is being renewed in 2024 and the sewer is in poor condition so lining in the near future is advised to avoid having to dig up the new pavement if defects worsen	200	57.6
S-MA50008165	KINSBOURNE GREEN	1ST MH N. OF WESTBOURNE CRES. (E. OF CL) TO MH AT WESTBOURNE CRES. (W.C	WWS	FULL SEGMENT LINER	\$32,615.50	Street is being renewed in 2024 and the sewer is in poor condition so lining in the near future is advised to avoid having to dig up the new pavement if defects worsen	250	93.9
S-MA60015748	LAKESHORE RD.	1ST MH N.OF CHANCELLOR DR TO MH AT CHANCELLOR DR	WWS	AUGMENTED FS LINER	\$48,800.00	EPR 56.6-59.6m - 2 service reconnects	250	118.3
S-MA60017960	MARSHALL CR(N.LEG)	MH AT MARSHALL CR(W.LEG) TO 1ST MH E OF MARSHALL CR(W.LEG)	LDS	FULL SEGMENT LINER	\$41,817.50	B, FM, CL, ID, IDJ	375	83.8
S-MA60017488	OAKENWALD AV	1ST MH W OF WOODGROVE ST TO MANHOLE AT WOODGROVE ST	WWS	FULL SEGMENT LINER	\$31,331.50	fractures	200	87.5
S-MA60016471	PEMBINA HWY	MH @ CHANCELLOR DR TO 1ST MH N OF CHANCELLOR DR	WWS	FULL SEGMENT LINER	\$51,929.00	Street is being renewed in 2025 and the sewer is in poor condition so lining in the near future is advised to avoid having to dig up the new pavement if defects worsen	375	97.4
S-MA60015806	PROVIDENCE PL	MH AT AUGUSTA DR - 1ST MH N OF AUGUSTA DR	WWS	FULL SEGMENT LINER	\$37,109.50		250	114.2
S-MA50013522	ST ANNES RD	MH AT AVONDALE RD TO MH AT REGAL AV	CS	FULL SEGMENT LINER	\$201,352.86	SSM (missing clay tiles)	900	93.2
S-MA50009895	ST DAVID PL (W LEG)	MH AT ST DAVID PL (S LEG) TO MH AT ST DAVID RD	CS	FULL SEGMENT LINER	\$36,681.50	Street is being renewed in 2025 and the sewer is in poor condition so lining in the near future is advised to avoid having to dig up the new pavement if defects worsen	200	112.8
S-MA40011892	VICTORIA AV E	1ST MH W OF KANATA ST TO MH AT KANATA ST	WWS	FULL SEGMENT LINER	\$30,475.50	Part of street is being renewed in 2024 and the sewer is in poor condition so lining in the near future is advised to avoid having to dig up the new pavement if defects worsen	200	83.3
S-MA60017186	WALLER AV	1ST MH E OF MARSHALL CR(E.LEG) TO 1ST MH W OF MARSHALL CR(E.LEG)	LDS	FULL SEGMENT LINER	\$42,513.00	FM, FC, CM, CC, SRI, SSS	300	85.5
S-MA60017068	WALLER AV(S.OF CL)	1ST MH E OF DONNELLY ST TO 2ND MH E OF DONNELLY ST	LDS	FULL SEGMENT LINER	\$43,904.00	B, HSV, FM - Crossbored private service also cracked and leaking into LDS.	375	89.0
S-MA60011788	WEATHERDON AV	MH AT STAFFORD (EPL) TO 1ST MH W WENTHWORTH ST	CS	FULL SEGMENT LINER	\$42,299.00	IMAGES AVAILABLE. FLCL, CC.	300	73.7
S-MA60011846	WEATHERDON AV	MH AT WENTWORTH ST TO 1ST MH E OF WENTWORTH ST	CS	FULL SEGMENT LINER	\$43,208.50	Street is being renewed in 2024 and the sewer is in poor condition so lining in the near future is advised to avoid having to dig up the new pavement if defects worsen	375	87.4
S-MA60013015	WICKLOW ST.	1ST MH N.OF NORTH DR TO 1ST MH N.OF WATERFORD AV.	WWS	FULL SEGMENT LINER	\$33,899.50	Street is being renewed in 2024 and the sewer is in poor condition so lining in the near future is advised to avoid having to dig up the new pavement if defects worsen	250	99.6
S-MA60017587	WICKLOW ST.	1ST MH N.OF DOWKER AV TO MH AT DOWKER AV.	LDS	FULL SEGMENT LINER	\$52,250.00	FM, B - Street is being renewed in 2024 and the sewer is in poor condition so lining in the near future is advised to avoid having to dig up the new pavement if defects worsen	300	113.9
S-MA40011253	WILLIAM NEWTON AV	MH AT ALLEN ST TO 1ST MH E OF ALLAN ST	CS	FULL SEGMENT LINER	\$42,860.75	CL, CM, FM, B, D	300	86.3
S-MA60017486	WOODGROVE ST.	MH AT OAKENWALD AV TO 1ST MH N.OF OAKENWALD AV.	WWS	FULL SEGMENT LINER	\$15,388.50	Multiple fractures	300	7.1
					\$1,849,423.76			