



59-2025 ADDENDUM 1

DUGALD ROAD PAVEMENT RENEWAL – PLESSIS ROAD TO RAVENHURST STREET

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: March 25, 2025
BY: Scott Suderman, P.Eng.
TELEPHONE NO. 204 782-7189

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2024-02-01

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

FORM B: PRICES

Replace: 59-2025 Form B: Prices with 59-2025 Addendum 1 - Form B: Prices. The following is a summary of changes incorporated in the replacement Bid/Proposal Submission:

- Form B(R1): Clarified the widths for Items A.24 i), ii) and iii)
 Changed the culvert gauge thickness for Items A.33 i) and ii), and Items A.34 i) and ii)
 Corrected the language on Items A.35 iii) and iv), and Items A.35 iii) and iv)

PART E – SPECIFICATIONS

- Revise: E17.4 to read: “Reverse Concrete Curb and Gutter (150 mm reveal ht, Barrier, Integral, 300 mm gutter pan width, 180 mm Plain Type 1 Concrete Pavement)” shall be measured by the lineal metre and paid for at the Contract Unit Price
- Revise: E17.5 to read: “Reverse Concrete Curb and Gutter (120 mm reveal ht, mountable, Integral, 300 mm gutter pan width, 180 mm Plain Type 1 Concrete Pavement)” shall be measured by the lineal metre and paid for at the Contract Unit Price.
- Revise: E17.6 to read: “Reverse Concrete Curb and Gutter (10 mm reveal ht, mountable, Integral, 450 mm width, 180 mm Plain Type 1 Concrete Pavement)” shall be measured by the lineal metre and paid for at the Contract Unit Price.
- Add: E12.6 Topsoil thickness to be 75mm.